U.S. National Stage of I. A. No. PCT/GB 2004/003823 I. A. Filing Date: September 10, 2004 Attorney Docket No. 124822.00102

IN THE CLAIMS:

Please make the following amendments to the claims as noted.

1. (original) A system for screening items of baggage, the system comprising

attaching to each baggage item at a check-in location within a terminal an electronic tag

which is periodically scanned as the item travels via a baggage sortation system between the

check-in location and a loading location, diverting all baggage items from the sortation

system to an explosive detection screening system housed within a prefabricated building

alongside the terminal, retaining for further inspection baggage items which are not cleared

by the explosive detection screening system and re-introducing cleared baggage items into

the sortation system for travel to the loading location.

2. (original) A system as claimed in claim 1 wherein the prefabricated building

is sited between an exit from a baggage hall of a terminal building and houses endless

conveyor belts for transporting baggage items to and from an EDS machine for screening

purposes.

3. (currently amended) A system as claimed in claim 1 or claim 2 wherein a

plurality of baggage screening conveyor belts are located within the prefabricated housing

each connected at one end to receive baggage items from a continuous loop conveyor and at

another end to feed baggage items onto the continuous loop conveyor, each one of the

plurality of screening conveyor belts having an EDS machine through which baggage items

pass.

- 2 -

U.S. National Stage of I. A. No. PCT/GB 2004/003823 I. A. Filing Date: September 10, 2004 Attorney Docket No. 124822.00102

- 4. (original) A system as claimed in claim 3 wherein the loop conveyor is linked to a baggage conveying system located within a terminal building through a continuous conveyor located within a tunnel which places the terminal building in communication with the prefabricated building, the tunnel located conveyor transporting baggage from the conveying system located within the terminal building to and from the continuous loop conveyor of the prefabricated building.
- 5. (currently amended) A system as claimed in claim 3 or claim 4 wherein each screening conveyor includes a holding station where items of baggage can be detained for inspection purposes.
- 6. (currently amended) A system as claimed in <u>claim 2</u> any one of claims 2 to 5 wherein each EDS machine is linked to a remote control room from which all EDS machines are controlled and from which X-ray images of baggage items can be inspected.

- 3 -